Illinois Department of Natural Resources

CERP code: 1606805
(Provided by CERP staff.)

COMPREHENSIVE ENVIRONMENTAL REVIEW PROCESS

Regional CERP code:	DEP-16-03	Project title:	BP Pipeline Repair		
Site name:	Des Plaines SFWA	Proposed start date:	ASAP--RUSH review requested		
Contact person:	Jeff Wepprecht; Barry Hart	Phone:	815-786-4067; 847-608-3100x32035	County:	Will
Township:	T33N	Range:	R9E	Section:	14

Project Description:

An anomaly has been detected in the wall of a petroleum pipeline that passes through Des Plaines SFWA. To repair the problem, the pipe has to be exposed by excavating earth above the pipe, identifying the cause of the anomaly, and making necessary repairs.

The excavation will be approximately 15 feet by 15 feet at the surface. The hole will be centered on the pipeline; therefore, it will be within the width of earth previously disturbed when the pipe was laid. Topsoil will be stockpiled separate from lower parent soil layers. After pipe repair is completed, the hole will be backfilled with parent soils first and then topsoil at the surface as before. The site will be restored to pre-excavation conditions as closely as possible.

Pipeline company contact:
Chad A. Workman
Contract Land Staff, LLC
Contract Right-of-Way Agent
BP Pipelines (North America) Inc.
Cell 217-638-5558
Chad.Workman@BP.com
Chad.Workman@contractlandstaff.com

Is work area in a Federal Aid Project boundary? Yes or No Federal Aid type:

Funding source: IDNR Capital— Heavy Equipment— Force Account—
Other State, Local, or Private agency— **British Petroleum Pipelines (North America) Inc.**
Federal Agency— Federal Program—

Approval by Site Superintendent (for all NON-CAPITAL projects, e.g., heavy equipment, force account, leases, r-o-w, etc.)

Signature, Site Superintendent: *Jeff Wepprecht (by B. Hart)* Date: February 1, 2016

CERP Staff Only
REVIEWS PERFORMED

	Approved	Approved w/ Restrictions	Comments
Threatened & Endangered Species Natural Areas/Nature Preserves	X		
Wetlands	X		
Cultural Resources	X		
Other	N/A		

Rich Lewis 2-1-16

Rich Lewis, CERP Program Manager
217–557–0480

Date

File: dep1603_BPPipelineRepair.docx